



AECOM

Taylor Run Infrastructure Stabilization Community Meeting 60% Design

July 20, 2026

This meeting is being recorded.





We want to hear from you!

- ▶ Use the Q&A box to submit during tonight's meeting
- ▶ Submit a comment using the Smartsheet Link:



- ▶ Public feedback and comments will be collected through Monday, July 27, 2026



Tonight's Agenda

- ▶ Project Review
- ▶ Proposed Approach
- ▶ Tree Preservation
- ▶ Erosion Control
- ▶ Landscape Plan
- ▶ Project Schedule
- ▶ Open Discussion and Q&A



Project Team



Transportation & Environmental Services City of Alexandria

Camille Liebnitzky, PE, ENVSP
Alex Haptemariam, PE, CFM
Daniel E. Medina, PhD, PE
Jesse E. Maines, MPA

AECOM


Lead Design Consultant

Brandon Alderman, CERP
Sean Bernheisel, PE



Project Review

- ▶ Summer 2023, a set of recommendations from the Consensus Building Group (CBG) for Taylor Run was approved by City Council.
- ▶ City Council approved all recommendations that met full consensus.
- ▶ Recommendations: [Appendix E Taylor Run Recommendations from CBG with City Council Note](#)






Project Location





Where will we be working?


- ▶ Four distinct areas, totaling 540 linear, non-continuous feet
- ▶ One construction project
- ▶ Total work area: 1.7 acres



Investigation of Sewer Pipelines in Stream Areas 2020-2021

- Consequence of Failure (CoF) based on:
 - Size of the pipe
 - Location of the pipe relative to other infrastructure
 - Proximity to waterbodies or resource protection areas
 - Proximity to significant upstream service
 - Accessibility of the pipe
- Likelihood of Failure (LoF) based on:
 - Condition of the pipe internal and external
 - Material and date installed
 - Has the pipe been rehabilitated recently?
- External Factors based on:
 - Stream bank erosion
 - Pipe encasement
 - Internal CIPP lining

Previously Seen
By CBG
November 2022, Tylin



Taylor Run Stream Crossings

Previously Seen
By CBG
November 2022, Tylin

Sewer ID	Pipe Material	Diameter (Inch)	External Risk Factor	Likelihood of Failure (LoF)	Consequence of Failure (CoF)	Overall Risk Score
000040SEWP (Upstream)	CIPP	10	5	2.1	4.80	24.0
009478SEWP (Downstream)	DIP	15	5	1	5.32	26.6

000040SEWP




000040SEWP



009478SEWP

009478SEWP



2014 Taylor Run Sanitary Sewer Crossing Failure

Concrete pipe broken and Cured-In-Place Pipe (CIPP) lining exposed



Previously Seen
By CBG
November 2022, Tylin

007529SSMH - Manhole

Previously Seen
By CBG
November 2022, Tylin





Project Goals



Protect critical, at-risk infrastructure (e.g., sewer pipes, manholes, outfalls, and trails)



Stabilize streambanks and reduce erosion near infrastructure assets



Preserve and protect mature trees and wetlands



Minimize limits of disturbance, vegetation removal, and construction impacts






What have we done so far?

- ✓ Existing condition assessment
- ✓ Topographic and Tree Survey
- ✓ Geotechnical Investigation
- ✓ Hydrologic and Hydraulic Modeling
- ✓ Sewer inspections using CCTV
- ✓ Wetland Delineation
- ✓ Pre-JPA Meeting completed with USACE
- ✓ JPA Application Drafted
- ✓ 60% Design Submission (Available Online)





Previously Seen
By CBG
September 2022, AECOM



Recommendation from CBG:

Upper Culvert protection:

A stone covering of the culvert walls facing the stream should be put in place and concrete rubble removed as appropriate.




RIPRAP PLUNGE POOL



Proposed Approach – Project Area 1



Boulder Weir and Pool




Rock Façade Finish



Existing Condition



Gravity Wall with Safety Railing



NRCS Plunge Pool

Upstream Crossing Before & After

Before



Previously Seen
By CBG
February 2023, Tylin

After




Sewer Crossing Protection

Previously Seen
By CBG
February 2023, Tylin



Sanitary sewer in concrete encasement protected by boulders



Concrete Encasement

Photo credits: Fairfax County South
Van Dorn Street Project



Proposed Approach: Project Area 2



Gravity Wall with Safety Railing



Existing condition of at-risk sanitary sewer line



Rock Façade Finish




Concrete Encasement



Boulder Weir and Pool

Manhole Before & After



Previously Seen
By CBG
February 2023, Tylin




Proposed Approach: Project Area 3




Gravity Wall with Safety Railing

Grading and Seeding



Existing Condition



Previously Seen
By CBG
February 2023, Tylin

28

Downstream Crossing Before & After

Before



After




Sewer Crossing Protection

Previously Seen
By CBG
February 2023, Tylin



Sanitary sewer in concrete encasement protected by boulders



Concrete Encasement


Photo credits: Fairfax County South
Van Dorn Street Project




Proposed Approach: Project Area 4



Rock Packing




Concrete Encasement



Gravity Wall with Safety Railing



Boulder Weir and Pool




Existing Condition



Innovative Design Approach

► Gravity wall vs. standard retaining wall



Gravity Wall

Standard Reinforced
Retaining Wall





Tree Preservation: Project Area 2

Living trees
proposed for
removal


2

Dead trees
proposed for
removal

2

Total trees
proposed for
removal

4





Tree Preservation: Project Area 3

Living trees
proposed for
removal


2

Dead trees
proposed for
removal

2

Total trees
proposed for
removal

4





Tree Preservation: Project Area 4

Living trees
proposed for
removal


2

Dead trees
proposed for
removal

5

Total trees
proposed for
removal

7



► The Consensus Building Group (CBG) in 2023 recommended the trees in bold for continued preservation



Minimal Disturbance and Replanting

- ▶ **Minimal disturbance**
 - ▶ Following “minimal intervention” set by CBG and approved by Council
- ▶ **Critical Root Zone Protection**
 - ▶ Mulch and deck matting proposed to protect tree roots
- ▶ **Native Plantings**
 - ▶ Replanting anticipates approximately 70 new canopy trees, 350 new understory trees/shrubs





Deck Mat/Construction Access Road



Tree Root Protection During Construction

► Timber mats

- Reduce soil stress up to 77% at 0.65 feet
- Reduce soil stress up to 60% at 1.30 feet



Loraine ten Damme, Matthias Stettler, Renato P. de Lima, Thomas Keller,
The benefit of using access materials for soil stress reduction depends on the material's properties and
vehicle mean ground pressure,
Journal of Terramechanics,
Volume 121,
2026,
101097,
ISSN 0022-4898,
<https://doi.org/10.1016/j.jterra.2025.101097>.



Construction Equipment



Excavator

▶ Approximately 30,000 lbs



Haul Truck

▶ Approximately 25,000 lbs



Erosion Control: Project Area 1



High Visibility/Tree Protection Fence



Pump Around Practice



Construction Access/Timber Matting



Tree Planking



Filter Bag



Erosion Control: Project Area 2



Pump Around Practice



High Visibility/Tree Protection Fence



Construction Access/Timber Matting



Super Silt Fence



Tree Planking



Filter Bag




Erosion Control: Project Area 3



Pump Around Practice



Temporary Bridge



Tree Planking



High Visibility/Tree Protection Fence




Filter Bag



Erosion Control: Project Area 4



Pump Around Practice



Stabilized Construction Entrance



Tree Planking



Construction Access/Timber Matting



Silt Fence



High Visibility/Tree Protection Fence



Filter Bag



FAQ: Can the project not use the stream for site access? Why does it need to use the trail?

- ▶ The project requires reliable access for construction equipment, materials, and personnel. The existing trail provides the most practical access while minimizing the need to create new disturbance elsewhere in the park. Using the stream channel as the primary access route is not feasible because large rocks, fallen trees, and other natural debris would make it difficult and unsafe for construction equipment to travel through the stream. Traveling within the stream could also increase impacts to the stream bed, banks, and aquatic habitat. The existing trail will be restored following construction.


Downstream Sewer Crossing & Exposed MH Construction Access

Fill Needed for Similar Construction Access as 2015 Taylor Run Crossing Interim Solution Project



2015

Photo Credit: Rod Simmons



Current

Photo Credit: Greeley and Hansen

Previously Seen
By CBG
February 2023, Tylin

Chinquapin Park Acidic Seepage Swamp Protection

- 69 recorded species
- Mainly located south of Alexandria Heritage Trail
- Wetland areas excluded from LOD
- Use combination of chain link fence and silt fence to protect wetlands from being disturbed



Photo Credits: Rod Simmons



Photo Credit: Greeley and Hansen

**Utilize Similar
Protection as 2015
Taylor Run Crossing
Interim Solution Project**

Previously Seen
By CBG
February 2023, Tylin



Wetland Delineation: 04/06/2026



- ▶ Wetland boundaries consistent with previously completed wetland delineation (August 2019)




Landscape Site Visit: 02/12/2026






Landscape Plan: Project Area 1






Landscape Plan: Project Area 2






Landscape Plan: Project Area 3





Landscape Plan: Project Area 4





Landscape Details: Tree Palette



Black Locust
Robinia pseudoacacia



Chestnut Oak
Quercus Montana



White Oak
Quercus alba



Tulip Poplar
Liriodendron Tulipifera



American Elm
Ulmus americana



Slippery Elm
Robinia pseudoacacia




Black Cherry
Prunus serotina



Red Maple
Acer rubrum



Sassafras
Sassafras albidum



American Holly
Ilex opaca



Eastern Red Cedar
Juniperus virginiana



Landscape Details: Understory Palette



Spicebush
Lindera benzoin



Witchhazel
Hamamelis virginiana



Mountain Laurel
Kalmia latifolia



Marginal Wood Fern
Dryopteris marginalis




FAQ: Can the project work outside of nesting season?

- ▶ There is no single nesting season that applies to all bird species. To minimize potential impacts, the City has shifted the anticipated construction start to Fall 2027, which is outside the nesting period for most bird species. The project will also comply with all applicable environmental requirements prior to construction.



Project Schedule





We want to hear from you!

- ▶ Submit a comment using the Smartsheet Link:



- ▶ Community feedback and comments will be collected through Monday, July 27, 2026



Thank you for attending!

► Contact Information:

Camille Liebnitzky, PE, ENV SP (City Sponsor Project Manager):
camille.liebnitzky@alexandriava.gov

Alex Haptemariam, PE, CFM (City Managing Project Manager):
alex.haptemariam@alexandriava.gov

► Project Website:

<https://www.alexandriava.gov/capital-projects/project/taylor-run-infrastructure-stabilization-project>



Resources

- ▶ [September 2022, Taylor Run Alternative Design, Minimal Impact](#) – Brandon Alderman, CERP, AECOM
- ▶ [November 2022, Taylor Run Sanitary Sewer Crossings, Presentation \(Part 1\)](#) -Erin Bevis-Carver, PE, Division Chief, T&ES/Sanitary Infrastructure Division, City of Alexandria and Dustin Dvorak, PE, Greeley-Hansen (Tylin)
- ▶ [February 2023, Taylor Run Sanitary Sewer Crossings, Presentation \(Part 2\)](#) - Erin Bevis-Carver, PE, Division Chief, T&ES/Sanitary Infrastructure Division, City of Alexandria and Dustin Dvorak, PE, Greeley-Hansen (Tylin)
- ▶ [February 2023, Taylor Run BMPs in the Watershed, Presentation](#) – Brian Rahal, PE, T&ES/Stormwater Management and Ehsanullah Hayat, T&ES/Stormwater Management
- ▶ [February 2023, Taylor Run Watershed Analysis: The Effects of Implementing Stormwater Facility Best Management Practices \(BMPs\) in the Watershed on the Stream Channel](#) – Brian Rahal, PE, T&ES/Stormwater Management, Ehsanullah Hayat, T&ES/Stormwater Management, Camille Liebnitzky, PE, T&ES/Stormwater Management, and Jesse Maines, Division Chief, T&ES/Stormwater Management
- ▶ [March 2023, Appendix E: Taylor Run Worksheet](#) – Institute of Engagement & Negotiation and the Taylor Run Consensus Building Group